### Infiltration BMPs: Caltrans Retrofit Pilot Study Experience

Brian Currier, PE
University of California, Davis
Center for Environmental and Water
Resources Engineering

### Infiltration for Stormwater Management...

Why?

 Reduce surface water discharges and comply with NPDES regulations


How?

Basins

Trenches

Siting and Design Criteria...


### Typical Basin Design



### Design Procedure Used...


- It varied...L.A. basin sized to drain in 36 hours
- S.D. basin sized to drain in 72 hours (maximum recommended)
- A=V/(T\*f)
  - A = area of basin,
  - V = capture volume,
  - f = field permeability,
  - T = drain time

### Typical Trench Design



### Infiltration Challenges...

- Stormwater treatment
- Vectors (Mosquito Habitat)
- Groundwater impacts



### Siting Criteria Used

- Minimum Field Permeability of 7mm/hr (0.27 in/hr)
- Minimum Groundwater Separation of 0.6 m to 1.2 m (2-4 ft)
- Other site size, access, and setback requirements

#### Site Selection Process

- Infiltration Basin Site Screening
  - 14 potential sites ->
  - 5 selected for field tests ->
  - Only 2 suitable sites
- Infiltration Trench Site Screening
  - 38 potential sites ->
  - 8 selected for field tests ->
  - Only 2 suitable sites

### Case Study Site Conditions

Site – BMP	Measured permeability mm/hr (in/hr)	Groundwater separation <sup>a</sup> m (ft)
San Diego Basin	22.3 (0.88)	0.6 (2)
Los Angeles Basin	5.8 (0.23)	9+ (30+)
Los Angeles Trench	40 (1.6)	0.6+ (2+)
San Diego Trench	31 (1.2)	0.6+ (2+)

### Infiltration Trench – S.D.



### Infiltration Trench – S.D.



### Infiltration Trench – L.A.



### Infiltration Basin – L.A.



### Failed Infiltration Basin (S.D.)




# Groundwater Quality Investigations

Vadose zone monitoring unsuccessful

 Groundwater monitoring too limited and short-term to draw reliable conclusions

# Groundwater Quality Investigations

Vadose (unsaturated)



Groundwater

#### Performance Notes

- 50% of installations performed poorly
- Poorly performing infiltration BMPs was not due to insufficient maintenance
- The S.D. trench doesn't work well, despite good field test results
- The L.A. Basin works well, despite marginal infiltration rates (conservative design)
- Unknown groundwater impact

# So how do we compensate for the variation in performance?

- Improve site investigations
- Revise siting criteria
- Use more conservative design procedure

### Improved Site Investigations

- Multiple permeability tests at multiple locations
- If within 3 m (10 ft), perform long term groundwater level monitoring
- Check soil conditions for evidence of rising groundwater

### Revised Siting Criteria

- Minimum Permeability:
  - 13 mm/hr (0.5 in/hr) is suggested in Maryland guidance
  - Lower if available land and high confidence in field tests
- Minimum Groundwater Separation:
  - 3 m (10 ft) separation would prevent siting in the failed San Diego location
  - 3 m is also suggested in literature as a minimum for groundwater protection
- Soil Type: NRCS Type A or B

### More conservative Design Procedure

- Do not design for maximum allowed drain time (72 hours)
- Consider using 48 hour maximum drain time – 6 hours is recommended in many references

## More conservative Design Procedure (cont.)

- Select Factor of Safety
  - FS of 0.5 applied to the lowest field measured permeability is recommended
  - Depends on soils, space available, expected maintenance intervals, and confidence in the field tests



### Options to Maintain Infiltration

#### Basins:

- Scarify as needed
- Remove sediment and regrade

#### Trenches:

- Top trench layer is removed/rock cleaned as needed
- Complete trench reconstruction

#### Cautions

- Can not remove sediments on trenches without rebuilding top portion
- Is current separation guidance sufficient to protect groundwater quality?
- Typical 'pretreatment' does little for dissolved constituents
- Greater permeability usually means less groundwater protection
- California has an anti-degradation policy (68-16) requiring discharges not to exceed background levels

### Acknowledgments

- Design
  - Montgomery Watson
  - RBF
- Maintenance and Monitoring
  - Law Crandall
  - Kinnetic Laboratories, Inc.

```
http://www.dot.ca.gov/hq/env/
stormwater/index.htm
```